



PROJECT PROFILE

B&J Catalano | Install Geofabric and Associated Works on
New Tailings Storage Facility (TSF)

CLIENT

B&J Catalano

PROJECT

TSF Re-Instatement

LOCATION

Golden Grove, Yalgoo WA

ADDITIONAL WORKS

- Excavate trench and install mega flow
- Rolling out Geofabric and Geomesh and weld together and sandbag
- Dig keyway to secure mesh and backfill
- Fabricate and install pressure relief wells
- Fabricate and install piezo wells

REQUIREMENT

Install Geofabric and Geo mesh along newly formed buttress

PIPE WORK

- Extend 355mm pipework in conjunction with wall raises
- Relocate tailings and return water lines

CONTRACT

Day rates

SERVICES AND EQUIPMENT PROVIDED

- Supervisor, Polywelder and Operators
- Supervisors vehicle and welding truck c/w generator
- 1 x Manitou Telehandlers c/w spreader bar
- 8.5 ton Excavator and pipe roller slings
- HF350 Polywelder
- 2 x Extrusion welder kits

