

PROJECT PROFILE

Saracen Metals | Pit Dewatering to Supply Mill with Process Water

CLIENT

Saracen Metals

PROJECT

Pit Dewatering to Supply Mill with Process Water

LOCATION

Banockburn,
Northern Goldfields WA

REQUIREMENT

- Install Pit Dewatering Infrastructure and Underground Inceptor Bores

PIPE WORK

Supply, Deliver and Install

- 320m x 160mm PN16 HDPE
- 680m x 225mm PN6.3 and PN16 HDPE
- 1,220m x 250mm PN6.3 HDPE
- 1,760m x 315mm PN6.3 HDPE
- 2,160m x 450mm PN6.3 HDPE

ADDITIONAL WORKS

- Installation of pit dewatering submersible pumps and electric cables
- Installation of bore pumps, headworks and starter panels
- Supply and install all poly fittings, bends and valves
- Supply and install culverts at road crossing

SERVICES AND EQUIPMENT PROVIDED

- Engineering design and drawings for pipeline
- Electrical Installation
- Supervisor, Polywelder and Operators
- Supervisors vehicle and welding truck c/w generator
- Manitou Telehandlers
- 13 ton Excavator
- Plakka boat c/w outboard motor
- Polywelders
 - 2 x T500 Tracstar
 - 2 x HF350
 - 2 x HF225
 - Delta 500



CONTRACT

Lump Sum